BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI
Office of the Executive Engineer, Dasarahalli Division
Schedule -B

NAME OF THE WORK: Providing CC Camera at Garbage block spots in ward no. 12

Sl. No	Description of work	Unit	Qty	Rate Quoted by Contractor Sri.K.Jagadish	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Supplying of Hikvision 8 channel NVR/DVR DS 7608NI-E1 (NVR default without HDD) (DATA RATE) complete as per the direction of Engineer-in-charge of the work	Each	6.00	16310.18	Rupees Sixteen Thousand Three Hundred Ten
2	Supplying of HikvisionPTZ Camera DS 2DE 7174-A with Pole mount and power supply (DATA RATE) complete as per the direction of Engineer-in-charge of the work	Each	6.00	62216.62	Rupees Sixty Two Thousand Two Hundred Sixteen and
3	Supplying of 2TB Hard disk - Seagate (DATA RATE) complete as per the direction of Engineer-in-charge of the work	Each	6.00	7634.55	Rupees Seven Thousand Six Hundred
4	Supplying of 6 port POE switch TP Link (DATA RATE) complete as per the direction of Engineer-in-charge of the work.	Each	6.00	2478.75	Rupees Two Thousand Four Hundred
5	Supplying of 4 pin spike pin cona/Reputed (DATA RATE) complete as per the direction of Engineer-in-charge of the work	Each	6.00	347.02	Rupees Three Hundred Forty Seven
6	Supplying of outdoor supportable CAD6/CAD5 cable (DATA RATE) complete as per the direction of Engineer-in-charge of the work	Mtr	1000.00	138.81	Rupees One Hundred Thirty Eight
7	Fabricating, Supplying and erecting swaged tublar pole of height.. Mtr having three sections and Providing two coats of red oxide paint and finished with two coats of enameled paint of approved quality and colour and M S base plate of suitable size welded at the bottom of the pole (as per IS) and 40mm dia GI / flexible PVC pipe of mtr. Length fitted to the heavy guage polycarbonate control box including 5 way connector of size 167x125x82mm for 7.5mm pole / 200x160x98 mm for remaining length of pole with front opening cover, with locking arrangements and suitable capacity MCB /DP switch. The pole shall be erected and cement concrete work (1:2:4) including excavation and refilling of plantingdepth of the pole to the ground level and the coping CC shall be upto 0.6 m above ground level as per IS 2713-7.1. Erection of light duty pole on foot path a) 7.5 m (4.5m Hb 114.3mm dia 4.05mm thick x 1.5m Hm 88.9mm dia 4.05mm thick x 1.5m Ht, 76.1mm dia 3.25 mm thick) as per IS 410 SP 5 (Base plate of size 300x300x6mm) complete as per the direction of Engineer-in-charge of the work	Each	6.00	8923.5	Rupees Eight Thousand Nine Hundred Twenty Three and Fifty Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

8	Supplying and fixing of monitor for viewing. Make SAMSUNG/ LG/PHILIPS/VIDEOCON (DATA RATE) complete as per the direction of Engineer-in-charge of the work	Each	6.00	9915.0	Rupees Nine Fifteen
9	Outdoor supportable CAD 6/ CAD5 cabling, Laying charges (DATA RATE) complete as per the direction of Engineer-in-charge of the work	Each	1100.00	138.81	Rupees Hundred Thirty Eight
10	Fabricating, Supplying and mounting MS box made out.. SWG suitable for floor/ wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size cd lamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enemeled metal paint etc., Complete b) 16 swg (PWD Ele SR 2014-15,complete as per the direction of Engineer-in-charge of the work	Sqcm	154000.00	0.33	Thirty Three Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer
Dasarahalli Division
BBMP

Signature of the Contractor

Scanned by CamScanner